

## NOTES

- 1. INSTALL SAFETY HANDRAIL IF SPECIFIED ON CONTRACT DRAWINGS
- 2. PRECAST UNIT MAY BE PROVIDED AS ALTERNATIVE WITH CONTRACT ADMINISTRATOR'S APPROVAL.
- 3. ALL STEEL COMPONENTS TO BE HOT DIPPED GALVANIZED AFTER FABRICATION.
- 4. SAFETY GRILLAGE TO BE WELDED AT ALL JOINTS AND CONNECTIONS EXCEPT AT ANCHOR BOLTS
- 5. REFER TO CONTRACT DRAWINGS FOR LOCATIONS AND SITE SPECIFIC DIMENSIONS. REFER TO SECTIONS 03200 AND FOR DETAILED SPECIFICATIONS.

DRAWING NUMBER: